



# AGRICULTURAL IRRIGATION LOADING CHART

## ASTM D2241: Plastic Irrigation Pipe (PIP) | Gasketed Integral Bell

20' LENGTH PIPE SEGMENTS					
Nominal Pipe Size	SKU	Approx. Weight Per Foot (lb/ft)	Joints Per Bundle	Lift Quantity	Feet Per Truckload
<b>SDR 41</b>					
6"	16206002010000	1.90	33	660	7,920
8"	16208002010000	3.30	14	280	4,480
10"	16210002010000	5.20	12	240	2,880
12"	16212002010000	75.00	16*	320	2,560
15"	16215002010000	11.80	6	120	1,440
18"	16218002010000	17.80	2/3/4/6	40/60/80/120	1,000
21"	16221002010000	24.80	4	80	640
24"	16224002010000	31.60	4	80	640
27"	tbd	40.40	3	60	480
<b>SDR 51</b>					
6"	16306002010000	1.60	33	660	7,920
8"	16308002010000	2.70	14	280	4,480
10"	16310002010000	4.20	12	240	2,880
12"	16312002010000	6.00	16*	320	2,560
15"	16315002010000	9.60	6	120	1,440
18"	16318002010000	14.40	2/3/4/6	40/60/80/120	1,000
21"	tbd	20.00	4	80	640
24"	16324002010000	25.50	4	80	640

22' LENGTH PIPE SEGMENTS					
Nominal Pipe Size	SKU	Approx. Weight Per Foot (lb/ft)	Joints Per Bundle	Lift Quantity	Feet Per Truckload
<b>SDR 41</b>					
15"	16215002210000	11.80	6	132	1584
18"	16218002210000	17.80	2/3/4/6	44, 66, 88, 132	1100
21"	16221002210000	24.80	4	88	704
24"	tbd	31.60	4	88	704
27"	tbd	40.40	3	66	528
<b>SDR 51</b>					
15"	16315002210000	9.60	6	132	1584
18"	16318002210000	14.40	2/3/4/6	44, 66, 88, 132	1100
21"	16321002210000	20.00	4	88	704
24"	16324002210000	25.50	4	88	704

**Note:**

1. These dimensions are for estimating purposes only.

\*Lodi, CA plant – 12" = 8pcs/lift